Conductive Concrete

Training Answers

- What depth is to be excavated when installing a precast base for the Cabinet?
 750mm
- 2) What depth is to be excavated for and in situ base?700mm
- 3) What is the usual area of excavation?As per the job pack issued
- 4) How many bags of Cubis San Earth are generally required per installation?4
- 5) Prior installation what is the first thing to consider and identify? Cabinet orientation
- 6) Which trench does the 16mm2 copper electrode run into? Telco
- 7) What do you do with the unused electrode tail?Coil it and put it into a length of Duct36 and Plug or cap it off.
- 8) What do you need to do to allow identification of the insulated earth link after installation? Attach Label
- 9) What documentation needs to be completed after installation?A55
- 10) Do you need to do an earth reading? No

